## 21-GP1-193 Economic Impact Data Sheet

Briefly summarize your proposal's primary economic impacts and benefits to building owners, tenants and businesses.

Adds new code section regulating compressed air systems. Language it taken from proposed Title 24 2022 language and is similar but much more comprehensive to City of Seattle requirements. Intent is that this would apply to process loads.

Increased first costs and decreased utility bills. The costs and saving are determined from Title 24 CASE Reports. In both reports portions of the requirements were evaluated in 4 prototypes. For each requirement, data from the prototype where it was least cost effective was used to evaluate the measure in the OFM calculator. Thus the estimate cost benefit is very conservative

Pipe Sizing, Monitoring, and Leak Testing for Compressed Air Systems. Final Case Report. Sept 2020. Prepared by AESC, Inc. and Energy Solutions. Available at: <a href="https://title24stakeholders.com/wp-content/uploads/2020/06/NR-compressed-Air Draft-CASE-Report.pdf">https://title24stakeholders.com/wp-content/uploads/2020/06/NR-compressed-Air Draft-CASE-Report.pdf</a>

Available at: <a href="https://title24stakeholders.com/wp-content/uploads/2020/01/T24-2013-Final-CASE-Report-AirCompressors.pdf">https://title24stakeholders.com/wp-content/uploads/2020/01/T24-2013-Final-CASE-Report-AirCompressors.pdf</a>

Provide your best estimate of the construction cost (or cost savings) of your code change proposal? (See OFM Life Cycle Cost <u>Analysis tool</u> and <u>Instructions</u>; use these <u>Inputs</u>. Webinars on the tool can be found <u>Here</u> and <u>Here</u>) \$0/square foot (For residential projects, also provide \$0/ dwelling unit)

Show calculations here, and list sources for costs/savings, or attach backup data pages

No independent cost estimate was made. Costs and saving are determined from Title 24 Case reports.

Requirement	T24 Worst Case	Initial Cost	Annual Energy Savings	Ongoing expense
Auto-shut down timer	Prototype 3	\$6173	7025kWh	
Trim Compressor	Operating Profile 3 / 25 hp	\$4000	8293kWh	
Pipe Sizing	Prototype 4	\$272982	210147 kWh	
Monitoring	Prototype 1	\$10685	42058 kWh	\$300/yr data services for 2 comps + \$500 every 5 for calibration
Leak Testing	Prototype 3	\$3342	6548 kWh	

**OFM Calculator Summary** 

**Smart Controls** 

Life Cycle Cost Analysis	BEST					
Alternative		Baseline		Alt. 1		Alt. 2
Energy Use Intenstity (kBtu/sq.ft)		#DIV/0!		#DIV/0!		#DIV/0!
1st Construction Costs	\$	-	\$	6,173	\$	-
PV of Capital Costs	\$	-	\$	15,237	\$	-
PV of Maintenance Costs	\$	=	\$	=	\$	-
PV of Utility Costs	\$	333,677	\$	310,236	\$	333,677
Total Life Cycle Cost (LCC)	\$	333,677	\$	325,474	\$	333,677
Net Present Savings (NPS)		N/A	\$	8,204	\$	-

Societal LCC takes into consideration the social cost of carbon dioxide emissions caused by operational energy consumption

(GHG) Social Life Cycle Cost		BEST	
GHG Impact from Utility Consumption	Baseline	Alt. 1	Alt. 2
Tons of CO2e over Study Period	2,059	1,915	2,059
% CO2e Reduction vs. Baseline	N/A	7%	0%
Present Social Cost of Carbon (SCC)	\$ 130,707	\$ 121,525	\$ 130,707
Total LCC with SCC	\$ 464,385	\$ 446,999	\$ 464,385
NPS with SCC	N/A	\$ 17,386	\$ -

## **Trim Compressor**

Life Cycle Cost Analysis	BEST							
Alternative	Baseline		Alt. 1		Alt. 2			
Energy Use Intenstity (kBtu/sq.ft)	#DIV/0!		#DIV/0!		#DIV/0!			
1st Construction Costs	\$ -	\$	4,000	\$	-			
PV of Capital Costs	\$ -	\$	9,873	\$	-			
PV of Maintenance Costs	\$ -	\$	-	\$	-			
PV of Utility Costs	\$ 333,677	\$	306,005	\$	333,677			
Total Life Cycle Cost (LCC)	\$ 333,677	\$	315,879	\$	333,677			
Net Present Savings (NPS)	N/A	\$	17,798	\$	-			

Societal LCC takes into consideration the social cost of carbon dioxide emissions caused by operational energy consumption

(GHG) Social Life Cycle Cost		BEST	
GHG Impact from Utility Consumption	Baseline	Alt. 1	Alt. 2
Tons of CO2e over Study Period	2,059	1,888	2,059
% CO2e Reduction vs. Baseline	N/A	8%	0%
Present Social Cost of Carbon (SCC)	\$ 130,707	\$ 119,868	\$ 130,707
Total LCC with SCC	\$ 464,385	\$ 435,747	\$ 464,385
NPS with SCC	N/A	\$ 28,638	\$ -

Life Cycle Cost Analysis	BEST					
Alternative		Baseline		Alt. 1		Alt. 2
Energy Use Intenstity (kBtu/sq.ft)		#DIV/0!		#DIV/0!		#DIV/0!
1st Construction Costs	\$	-	\$	272,982	\$	-
PV of Capital Costs	\$	-	\$	673,819	\$	-
PV of Maintenance Costs	\$	-	\$	-	\$	=
PV of Utility Costs	\$	3,336,772	\$	2,635,559	\$	3,336,772
Total Life Cycle Cost (LCC)	\$	3,336,772	\$	3,309,378	\$	3,336,772
Net Present Savings (NPS)		N/A	\$	27,394	\$	-

Societal LCC takes into consideration the social cost of carbon dioxide emissions caused by operational energy consumption

(GHG) Social Life Cycle Cost	BEST					
GHG Impact from Utility Consumption	Baseline		Alt. 1		Alt. 2	
Tons of CO2e over Study Period	20,592		16,265		20,592	
% CO2e Reduction vs. Baseline	N/A		21%		0%	
Present Social Cost of Carbon (SCC)	\$ 1,307,074	\$	1,032,396	\$	1,307,074	
Total LCC with SCC	\$ 4,643,845	\$	4,341,774	\$	4,643,845	
NPS with SCC	N/A	\$	302,071	\$	-	

## Monitoring

Life Cycle Cost Analysis	BEST						
Alternative	Baseline		Alt. 1		Alt. 2		
Energy Use Intenstity (kBtu/sq.ft)	#DIV/0!		#DIV/0!		#DIV/0!		
1st Construction Costs	\$ -	\$	10,685	\$	-		
PV of Capital Costs	\$ -	\$	26,374	\$	-		
PV of Maintenance Costs	\$ -	\$	13,601	\$	-		
PV of Utility Costs	\$ 3,336,772	\$	3,196,434	\$	3,336,772		
Total Life Cycle Cost (LCC)	\$ 3,336,772	\$	3,236,409	\$	3,336,772		
Net Present Savings (NPS)	N/A	\$	100,362	\$	-		

Societal LCC takes into consideration the social cost of carbon dioxide emissions caused by operational energy consumption

(GHG) Social Life Cycle Cost			BEST	
GHG Impact from Utility Consumption		Baseline	Alt. 1	Alt. 2
Tons of CO2e over Study Period		20,592	19,726	20,592
% CO2e Reduction vs. Baseline		N/A	4%	0%
Present Social Cost of Carbon (SCC)	\$	1,307,074	\$ 1,252,101	\$ 1,307,074
Total LCC with SCC	\$	4,643,845	\$ 4,488,510	\$ 4,643,845
NPS with SCC	_	N/A	\$ 155,335	\$ -

## **Leak Detection**

Life Cycle Cost Analysis	BEST							
Alternative	Baseline		Alt. 1		Alt. 2			
Energy Use Intenstity (kBtu/sq.ft)	#DIV/0!		#DIV/0!		#DIV/0!			
1st Construction Costs	\$ -	\$	3,342	\$	=			
PV of Capital Costs	\$ -	\$	8,249	\$	-			
PV of Maintenance Costs	\$ -	\$	-	\$	-			
PV of Utility Costs	\$ 3,336,772	\$	3,314,923	\$	3,336,772			
Total Life Cycle Cost (LCC)	\$ 3,336,772	\$	3,323,172	\$	3,336,772			
Net Present Savings (NPS)	N/A	\$	13,600	\$	-			

Societal LCC takes into consideration the social cost of carbon dioxide emissions caused by operational energy consumption

(GHG) Social Life Cycle Cost		BEST	
GHG Impact from Utility Consumption	Baseline	Alt. 1	Alt. 2
Tons of CO2e over Study Period	20,592	20,457	20,592
% CO2e Reduction vs. Baseline	N/A	1%	0%
Present Social Cost of Carbon (SCC)	\$ 1,307,074	\$ 1,298,515	\$ 1,307,074
Total LCC with SCC	\$ 4,643,845	\$ 4,621,687	\$ 4,643,845
NPS with SCC	N/A	\$ 22,159	\$ -

List any code enforcement time for additional plan review or inspections that your proposal will require, in hours per permit application:
This proposal will require jurisdictions to review compressed air designs and verify testing and monitoring. A complete guess but maybe 4 hours per permit that has systems of this scale which is a small fraction of the total
permits.
All questions must be answered to be considered complete. Incomplete proposals will not be accepted.